

Nominal	OD Inches		SCHEDULE	WALL	ID	WEIGHT/ FT
18"	18.000"		10S	0.188"	17.624"	35.76
18"	18.000"	10		0.250"	17.500"	47.39
18"	18.000"	20		0.312"	17.376"	58.94
18"	18.000"	STD	40S	0.375"	17.250"	70.59
18"	18.000"	30		0.438"	17.124"	82.15
18"	18.000"	XS		0.500"	17.000"	93.45
18"	18.000"	60		0.625"	16.876"	104.67
18"	18.000"	80		0.750"	16.750"	138.17
18"	18.000"	100		0.938"	16.724"	170.92
18"	18.000"	120		1.125"	16.588"	207.96
18"	18.000"	140		1.375"	16.250"	244.14
18"	18.000"	160		1.781"	15.718"	309.79

20"	20.000"		10S	0.219"	19.562"	41.6
20"	20.000"				19.500"	47
20"	20.000"	20	40S	0.281"	19.238"	56
20"	20.000"	30	60	0.344"	19.000"	69
20"	20.000"	40		0.406"	18.812"	81
20"	20.000"	50		0.469"	18.376"	94
20"	20.000"	60		0.531"	17.938"	107
20"	20.000"	80		0.694"	17.438"	139
20"	20.000"	100		0.857"	17.000"	171
20"	20.000"	120		1.020"	16.562"	203
20"	20.000"	140		1.183"	16.562"	235
20"	20.000"	160		1.544"	16.562"	299

22"	22.000"	10	10S	0.250"	21.500"	43.07	
22"	22.000"	STD	20	40S	0.375"	21.250"	58.61
22"	22.000"	XS	30	80S	0.500"	21.000"	74.81
22"	22.000"	60		0.625"	20.750"	91.41	
22"	22.000"	80		0.750"	20.500"	108.01	
22"	22.000"	100		0.875"	20.250"	124.61	
22"	22.000"	120		1.000"	20.000"	141.21	
22"	22.000"	140		1.125"	19.750"	157.81	
22"	22.000"	160		1.250"	19.500"	174.41	

Nominal	OD Inches		SCHEDULE		WALL	ID	WEIGHT/ FT
24"	24.000"		10	10S	0.250"	23.500"	63.41
24"	24.000"	STD	20	40S	0.375"	23.250"	94.62
24"	24.000"	XS		80S	0.500"	23.000"	125.49
24"	24.000"	30			0.562"	22.876"	140.68
24"	24.000"	40			0.688"	22.624"	171.29
24"	24.000"	60			0.969"	22.062"	238.35
24"	24.000"	80			1.219"	21.562"	296.58
24"	24.000"	100			1.531"	20.938"	367.39
24"	24.000"	120			1.812"	20.376"	429.93
24"	24.000"	140			2.062"	19.876"	483.1
24"	24.000"	160			2.344"	19.312"	542.13
26"	26.000"		10		0.312"	25.376"	85.6
26"	26.000"	STD		40S	0.375"	25.250"	102.63
26"	26.000"	XS		80S	0.500"	25.000"	136.17
28"	28.000"		10		0.312"	27.376"	92.26
28"	28.000"	STD		40S	0.375"	27.250"	110.64
28"	28.000"		20	80S	0.500"	27.000"	146.85
28"	28.000"		30		0.625"	26.750"	182.73
30"	30.000"		10		0.312"	29.376"	98.93
30"	30.000"	STD		40S	0.375"	29.250"	118.65
30"	30.000"	XS	20	80S	0.500"	29.000"	157.53
30"	30.000"		30		0.625"	28.750"	196.08
32"	32.000"		10		0.312"	31.376"	105.59
32"	32.000"	STD			0.375"	31.250"	126.66
32"	32.000"		20		0.500"	31.000"	168.21
32"	32.000"		30		0.625"	30.750"	209.43
32"	32.000"		40		0.688"	30.264"	230.08
34"	34.000"		10		0.312"	33.376"	112.25
34"	34.000"	STD			0.375"	33.250"	134.67
34"	34.000"		20		0.500"	33.000"	178.89
34"	34.000"		30		0.625"	32.750"	222.78
34"	34.000"		40		0.688"	32.624"	244.77
36"	36.000"		10		0.312"	35.376"	118.92
36"	36.000"	STD		40S	0.375"	35.250"	142.68
36"	36.000"	XS		80S	0.500"	35.000"	189.57

Nominal	OD Inches		SCHEDULE	WALL	ID	WEIGHT/ FT	
42"	42.000"	STD		40S	0.375"	41.250"	166.71
42"	42.000"	XS		80S	0.500"	41.000"	221.61
42"	42.000"		30		0.625"	40.750"	276.18
42"	42.000"		40		0.750"	40.500"	330.41
48"	48.000"	STD		40S	0.375"	47.250"	190.74
48"	48.000"	XS		80S	0.500"	47.000"	253.65

